08/917305
5000

PCT/SE97/00891

PATENT COOPERATION TREATY

From the INTERNATIONAL BUREAU

PCT

NOTIFICATION OF ELECTION

(PCT Rule 61.2)

To:

United States Patent and Trademark Office
(Box PCT)
Crystal Plaza 2
Washington, DC 20231
ETATS-UNIS D'AMERIQUE

in its capacity as elected Office

Date of mailing (day/month/year) 28 January 1998 (28.01.98)	
International application No. PCT/SE97/00891	**Applicant's or agent's file reference** P 97-233/NH
International filing date (day/month/year) 27 May 1997 (27.05.97)	**Priority date** (day/month/year) 29 May 1996 (29.05.96)
Applicant LEIJON, Mats et al	29 NOV 98

1. The designated Office is hereby notified of its election made:

   [X] in the demand filed with the International Preliminary Examining Authority on:

   22 December 1997 (22.12.97)

   [ ] in a notice effecting later election filed with the International Bureau on:

2. The election [X] was

   [ ] was not

   made before the expiration of 19 months from the priority date or, where Rule 32 applies, within the time limit under Rule 32.2(b).

The International Bureau of WIPO **34, chemin des Colombettes** **1211 Geneva 20, Switzerland** Facsimile No.: (41-22) 740.14.35	Authorized officer M. Abidine Telephone No.: (41-22) 338.83.38

Form PCT/IB/331 (July 1992)

1857201

08/973305

US/1

PATENT COOPERATION TREATY

From the INTERNATIONAL BUREAU

PCT

COMMUNICATION OF
INTERNATIONAL APPLICATIONS

(PCT Article 20)

To:

United States Patent and Trademark
Office
(Box PCT)
Crystal Plaza 2
Washington, DC 20231
ETATS-UNIS D'AMERIQUE

in its capacity as designated Office

Date of mailing:
22 January 1998 (22.01.98)

The International Bureau transmits herewith copies of the international applications having the following international application numbers and international publication numbers:

International application no.:	International publication no.:
PCT/SE97/00891	WO97/45926

CORRECTED VERSION
VERSION CORRIGEE

The International Bureau of WIPO **34, chemin des Colombettes** **1211 Geneva 20, Switzerland** Facsimile No.: (41-22) 740.14.35	Authorized officer: J. Zahra Telephone No.: (41-22) 338.83.38

Form PCT/IB/349 (July 1992)

1848464

INTERNATIONAL SEARCH REPORT

International application No.
PCT/SE 97/00891

A. CLASSIFICATION OF SUBJECT MATTER

IPC6: H02K 3/40
According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC6: H02K

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

SE,DK,FI,NO classes as above

Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

WPI

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	US 5036165 A (R.K. ELTON ET AL.), 30 July 1991 (30.07.91), column 2, line 27 - line 31, figure 1 --	1-34
A	US 4429244 A (P.Z. NIKITIN ET AL.), 31 January 1984 (31.01.84), column 1, line 10 - line 58 --	1-34

☐ Further documents are listed in the continuation of Box C. ☒ See patent family annex.

* Special categories of cited documents:
"A" document defining the general state of the art which is not considered to be of particular relevance
"E" erlier document but published on or after the international filing date
"L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)
"O" document referring to an oral disclosure, use, exhibition or other means
"P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
"X" document of particular relevance: the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
"Y" document of particular relevance: the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art
"&" document member of the same patent family

Date of the actual completion of the international search	Date of mailing of the international search report
18 November 1997	25 -11- 1997
Name and mailing address of the ISA/ Swedish Patent Office Box 5055, S-102 42 STOCKHOLM	Authorized officer Magnus Hjalmarsson

INTERNATIONAL SEARCH REPORT

Information on patent family members

01/10/97

International application No.
PCT/SE 97/00891

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
US 5036165 A	30/07/91	US 5066881 A	19/11/91
		US 5067046 A	19/11/91
		CA 1245270 A	22/11/88
		US 4853565 A	01/08/89
US 4429244 A	31/01/84	CA 1167898 A	22/05/84
		CH 663120 A,B	13/11/87
		DE 3050139 T	25/03/82
		FR 2473804 A,B	17/07/81
		GB 2081523 A,B	17/02/82
		JP 56501707 T	19/11/81
		SU 961048 A	23/09/82
		WO 8101775 A	25/06/81

PCT WORLD INTELLECTUAL PROPERTY ORGANIZATION
International Bureau

INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) **International Patent Classification** 6 : **H02K 3/40** | **A3**

(11) **International Publication Number:** **WO 97/45926**

(43) **International Publication Date:** 4 December 1997 (04.12.97)

(21) **International Application Number:** PCT/SE97/00891

(22) **International Filing Date:** 27 May 1997 (27.05.97)

(30) **Priority Data:**

9602079-7	29 May 1996 (29.05.96)	SE
9602078-9	29 May 1996 (29.05.96)	SE
9700335-4	3 February 1997 (03.02.97)	SE
9700347-9	3 February 1997 (03.02.97)	SE

(71) **Applicant** *(for all designated States except US)*: ASEA BROWN BOVERI AB [SE/SE]; S-721 83 Västerås (SE).

(72) **Inventors; and**
(75) **Inventors/Applicants** *(for US only)*: LEIJON, Mats [SE/SE]; Hyvlargatan 5, S-723 35 Västerås (SE). BERGGREN, Bertil [SE/SE]; Rönnbergagatan 2 B, S-723 46 Västerås (SE). GERTMAR, Lars [SE/SE]; Humlegatan 6, S-722 26 Västerås (SE). NYGREN, Jan-Anders [SE/SE]; Karlfeldtsgatan 27 B, S-722 22 Västerås (SE). SÖRENSEN, Erland [SE/SE]; Gudruns väg 32, S-723 55 Västerås (SE).

(74) **Agent:** HOPFGARTEN, Nils; L.A. Groth & Co., KB, P.O. Box 6107, S-102 32 Stockholm (SE).

(81) **Designated States:** AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CU, CZ, CZ (Utility model), DE, DE (Utility model), DK, DK (Utility model), EE, ES, FI, FI (Utility model), GB, GE, GH, HU, IL, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, TJ, TM, TR, TT, UA, UG, US, UZ, VN, YU, ARIPO patent (GH, KE, LS, MW, SD, SZ, UG), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, ML, MR, NE, SN, TD, TG).

Published
With international search report.
Before the expiration of the time limit for amending the claims and to be republished in the event of the receipt of amendments.

(88) **Date of publication of the international search report:**
22 January 1998 (22.01.98)

(54) **Title:** AN ELECTRIC HIGH VOLTAGE AC MACHINE

(57) **Abstract**

An electric high voltage AC machine intended to be directly connected to a distribution or transmission network (16) comprises at least one winding. This winding comprises at least one current-carrying conductor, a first layer having semiconducting properties provided around said conductor, a solid insulating layer provided around said first layer, and a second layer having semiconducting properties provided around said insulating layer. In addition grounding means (18, 24, 26, 28) are provided to connect at least one point of said winding to ground.



FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	**ES**	Spain	**LS**	Lesotho	**SI**	Slovenia
AM	Armenia	**FI**	Finland	**LT**	Lithuania	**SK**	Slovakia
AT	Austria	**FR**	France	**LU**	Luxembourg	**SN**	Senegal
AU	Australia	**GA**	Gabon	**LV**	Latvia	**SZ**	Swaziland
AZ	Azerbaijan	**GB**	United Kingdom	**MC**	Monaco	**TD**	Chad
BA	Bosnia and Herzegovina	**GE**	Georgia	**MD**	Republic of Moldova	**TG**	Togo
BB	Barbados	**GH**	Ghana	**MG**	Madagascar	**TJ**	Tajikistan
BE	Belgium	**GN**	Guinea	**MK**	The former Yugoslav Republic of Macedonia	**TM**	Turkmenistan
BF	Burkina Faso	**GR**	Greece			**TR**	Turkey
BG	Bulgaria	**HU**	Hungary	**ML**	Mali	**TT**	Trinidad and Tobago
BJ	Benin	**IE**	Ireland	**MN**	Mongolia	**UA**	Ukraine
BR	Brazil	**IL**	Israel	**MR**	Mauritania	**UG**	Uganda
BY	Belarus	**IS**	Iceland	**MW**	Malawi	**US**	United States of America
CA	Canada	**IT**	Italy	**MX**	Mexico	**UZ**	Uzbekistan
CF	Central African Republic	**JP**	Japan	**NE**	Niger	**VN**	Viet Nam
CG	Congo	**KE**	Kenya	**NL**	Netherlands	**YU**	Yugoslavia
CH	Switzerland	**KG**	Kyrgyzstan	**NO**	Norway	**ZW**	Zimbabwe
CI	Côte d'Ivoire	**KP**	Democratic People's Republic of Korea	**NZ**	New Zealand		
CM	Cameroon			**PL**	Poland		
CN	China	**KR**	Republic of Korea	**PT**	Portugal		
CU	Cuba	**KZ**	Kazakstan	**RO**	Romania		
CZ	Czech Republic	**LC**	Saint Lucia	**RU**	Russian Federation		
DE	Germany	**LI**	Liechtenstein	**SD**	Sudan		
DK	Denmark	**LK**	Sri Lanka	**SE**	Sweden		
EE	Estonia	**LR**	Liberia	**SG**	Singapore		

8246

PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

International Application No.

International Filing Date

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference *(if desired) (12 characters maximum)* P 97-233/NH /uh

Box No. I TITLE OF INVENTION

AN ELECTRIC HIGH VOLTAGE AC MACHINE

Box No. II APPLICANT

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)*

Asea Brown Boveri AB

S-721 83 VÄSTERÅS
Sweden

☐ This person is also inventor.

Telephone No.

Facsimile No.

Teleprinter No.

State *(i.e. country)* of nationality: SE

State *(i.e. country)* of residence: SE

This person is applicant for the purposes of: ☐ all designated States ☒ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)*

LEIJON, Mats

Hyvlargatan 5

S-723 35 VÄSTERÅS
Sweden

This person is:

☐ applicant only

☒ applicant and inventor

☐ inventor only *(If this check-box is marked, do not fill in below.)*

State *(i.e. country)* of nationality: SE

State *(i.e. country)* of residence: SE

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

☒ Further applicants and/or (further) inventors are indicated on a continuation sheet.

Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as: ☒ agent ☐ common representative

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

L.A.GROTH & Co.KB
HOPFGARTEN, Nils et al.
Box 6107
S-102 32 STOCKHOLM
Sweden

Telephone No. +46 - 8 - 729 91 00

Facsimile No. +46 - 8 - 31 67 67

Teleprinter No.

☐ Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

Continuation of Box No. III FURTHER APPLICANTS AND/OR (FURTHER) INVENTORS

If none of the following sub-boxes is used, this sheet is not to be included in the request.

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)*

BERGGREN, Bertil
Rönnbergagatan 2 B

S-723 46 VÄSTERÅS
Sweden

This person is:
- ☐ applicant only
- ☒ applicant and inventor
- ☐ inventor only *(If this check-box is marked, do not fill in below.)*

State *(i.e. country)* of nationality: SE

State *(i.e. country)* of residence: SE

This person is applicant for the purposes of:
- ☐ all designated States
- ☐ all designated States except the United States of America
- ☒ the United States of America only
- ☐ the States indicated in the Supplemental Box

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)*

GERTMAR, Lars
Humlegatan 6

S-722 26 VÄSTERÅS
Sweden

This person is:
- ☐ applicant only
- ☒ applicant and inventor
- ☐ inventor only *(If this check-box is marked, do not fill in below.)*

State *(i.e. country)* of nationality: SE

State *(i.e. country)* of residence: SE

This person is applicant for the purposes of:
- ☐ all designated States
- ☐ all designated States except the United States of America
- ☒ the United States of America only
- ☐ the States indicated in the Supplemental Box

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)*

NYGREN, Jan-Anders
Karlfeldtsgatan 27 B

S-722 22 VÄSTERÅS
Sweden

This person is:
- ☐ applicant only
- ☒ applicant and inventor
- ☐ inventor only *(If this check-box is marked, do not fill in below.)*

State *(i.e. country)* of nationality: SE

State *(i.e. country)* of residence: SE

This person is applicant for the purposes of:
- ☐ all designated States
- ☐ all designated States except the United States of America
- ☒ the United States of America only
- ☐ the States indicated in the Supplemental Box

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below.)*

SÖRENSEN, Erland
Gudruns väg 32

S-723 55 VÄSTERÅS
Sweden

This person is:
- ☐ applicant only
- ☒ applicant and inventor
- ☐ inventor only *(If this check-box is marked, do not fill in below.)*

State *(i.e. country)* of nationality: SE

State *(i.e. country)* of residence: SE

This person is applicant for the purposes of:
- ☐ all designated States
- ☐ all designated States except the United States of America
- ☒ the United States of America only
- ☐ the States indicated in the Supplemental Box

☐ Further applicants and/or (further) inventors are indicated on another continuation sheet.

Box No.V DESIGNATION OF STATES

The following designations are hereby made under Rule 4.9(a) *(mark the applicable check-boxes; at least one must be marked)*:

Regional Patent

☒ AP ARIPO Patent: KE Kenya, LS Lesotho, MW Malawi, SD Sudan, SZ Swaziland, UG Uganda, and any other State which is a Contracting State of the Harare Protocol and of the PCT

☒ EA Eurasian Patent: AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT

☒ EP European Patent: AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, and any other State which is a Contracting State of the European Patent Convention and of the PCT

☒ OA OAPI Patent: BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT *(if other kind of protection or treatment desired, specify on dotted line)* .....

National Patent *(if other kind of protection or treatment desired, specify on dotted line)*:

☒ AL Albania .....
☒ AM Armenia .....
☒ AT Austria .....
☒ AU Australia .....
☒ AZ Azerbaijan
☒ BA Bosnia and Herzegovina
☒ BB Barbados
☒ BG Bulgaria .....
☒ BR Brazil .....
☒ BY Belarus
☒ CA Canada
☒ CH and LI Switzerland and Liechtenstein
☒ CN China .....
☒ CU Cuba .....
☒ CZ Czech Republic and utility model .....
☒ DE Germany and utility model .....
☒ DK Denmark and utility model .....
☒ EE Estonia .....
☒ ES Spain .....
☒ FI Finland and utility model .....
☒ GB United Kingdom
☒ GE Georgia .....
☒ HU Hungary .....
☒ IL Israel .....
☒ IS Iceland
☒ JP Japan .....
☒ KE Kenya .....
☒ KG Kyrgyzstan .....
☒ KP Democratic People's Republic of Korea .....
☒ KR Republic of Korea .....
☒ KZ Kazakstan .....
☒ LC Saint Lucia
☒ LK Sri Lanka
☒ LR Liberia
☒ LS Lesotho .....
☒ LT Lithuania
☒ LU Luxembourg .....
☒ LV Latvia
☒ MD Republic of Moldova .....
☒ MG Madagascar .....
☒ MK The former Yugoslav Republic of Macedonia .....
☒ MN Mongolia
☒ MW Malawi .....
☒ MX Mexico .....
☒ NO Norway
☒ NZ New Zealand .....
☒ PL Poland .....
☒ PT Portugal .....
☒ RO Romania
☒ RU Russian Federation .....
☒ SD Sudan
☒ SE Sweden
☒ SG Singapore
☒ SI Slovenia .....
☒ SK Slovakia .....
☒ TJ Tajikistan .....
☒ TM Turkmenistan .....
☒ TR Turkey .....
☒ TT Trinidad and Tobago .....
☒ UA Ukraine .....
☒ UG Uganda .....
☒ US United States of America .....
☒ UZ Uzbekistan .....
☒ VN Viet Nam .....

Check-boxes reserved for designating States (for the purposes of a national patent) which have become party to the PCT after issuance of this sheet:

☒ YU Jugoslavien (fr. 1997-02-01)
☒ GH Ghana (AP) (fr. 1997-02-26)
☐ .....
☐ .....

In addition to the designations made above, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except the designation(s) of _____.
The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. *(Confirmation of a designation consists of the filing of a notice specifying that designation and the payment of the designation and confirmation fees. Confirmation must reach the receiving Office within the 15-month time limit.)*

Box No. VI PRIORITY CLAIM Further priority claims are indicated in the Supplemental Box ☒

The priority of the following earlier application(s) is hereby claimed:

Country *(in which, or for which, the application was filed)*	Filing Date *(day/month/year)*	Application No.	Office of filing *(only for regional or international application)*
item (1) Sweden	29 May 1996 (29.05.1996)	Jan 29, 97 9602079-7	
item (2) Sweden	29 May 1996 (29.05.1996)	9602078-9	
item (3) Sweden	03 February 1997 (03.02.1997)	9700335-4	

Mark the following check-box if the certified copy of the earlier application is to be issued by the Office which for the purposes of the present international application is the receiving Office (a fee may be required):

☒ The receiving Office is hereby requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) identified above as item(s): (1), (2), (3), (4)

Box No. VII INTERNATIONAL SEARCHING AUTHORITY

Choice of International Searching Authority (ISA) *(If two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used)*: ISA / SE

Earlier search *Fill in where a search (international, international-type or other) by the International Searching Authority has already been carried out or requested and the Authority is now requested to base the international search, to the extent possible, on the results of that earlier search. Identify such search or request either by reference to the relevant application (or the translation thereof) or by reference to the search request:*

Country (or regional Office):	Date *(day/month/year)*:	Number:
Sweden	29 May 1996	SE 96/00648

Box No. VIII CHECK LIST

This international application contains the following number of sheets:

1. request	5	sheets
2. description	12	sheets
3. claims	5	sheets
4. abstract	1	sheets
5. drawings	5	sheets
Total	28	sheets

This international application is accompanied by the item(s) marked below:

1. ☐ separate signed power of attorney
2. ☐ copy of general power of attorney
3. ☐ statement explaining lack of signature
4. ☐ priority document(s) *identified in Box No. VI as item(s):*
5. ☐ fee calculation sheet
6. ☐ separate indications concerning deposited microorganisms
7. ☐ nucleotide and/or amino acid sequence listing (diskette)
8. ☐ other *(specify)*:

Figure No. 6 of the drawings (if any) should accompany the abstract when it is published.

Box No. IX SIGNATURE OF APPLICANT OR AGENT

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).

L.A.GROTH & Co.KB

Nils Hopfgarten

For receiving Office use only

1. Date of actual receipt of the purported international application:	2. Drawings: ☐ received: ☐ not received:
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:	
4. Date of timely receipt of the required corrections under PCT Article 11(2):	
5. International Searching Authority specified by the applicant: ISA /	6. ☐ Transmittal of search copy delayed until search fee is paid

For International Bureau use only

Date of receipt of the record copy by the International Bureau:

Supplemental Box *If the Supplemental Box is not used, this sheet need not be included in the request.*

Use this box in the following cases:

1. If, in any of the Boxes, the space is insufficient to furnish all the information:	*in such case, write "Continuation of Box No. ..." [indicate the number of the Box] and furnish the information in the same manner as required according to the captions of the Box in which the space was insufficient;*
in particular:	
(i) if more than two persons are involved as applicants and/or inventors and no "continuation sheet" is available:	*in such case, write "Continuation of Box No. III" and indicate for each additional person the same type of information as required in Box No. III. The country of the address indicated in this Box is the applicant's State (i.e. country) of residence if no State of residence is indicated below;*
(ii) if, in Box No. II or in any of the sub-boxes of Box No. III, the indication "the States indicated in the Supplemental Box" is checked:	*in such case, write "Continuation of Box No. II" or "Continuation of Box No. III" or "Continuation of Boxes No. II and No. III" (as the case may be), indicate the name of the applicant(s) involved and, next to (each) such name, the State(s) (and/or, where applicable, ARIPO, Eurasian, European or OAPI patent) for the purposes of which the named person is applicant;*
(iii) if, in Box No. II or in any of the sub-boxes of Box No. III, the inventor or the inventor/applicant is not inventor for the purposes of all designated States or for the purposes of the United States of America:	*in such case, write "Continuation of Box No. II" or "Continuation of Box No. III" or "Continuation of Boxes No. II and No. III" (as the case may be), indicate the name of the inventor(s) and, next to (each) such name, the State(s) (and/or, where applicable, ARIPO, Eurasian, European or OAPI patent) for the purposes of which the named person is inventor;*
(iv) if, in addition to the agent(s) indicated in Box No. IV, there are further agents:	*in such case, write "Continuation of Box No. IV" and indicate for each further agent the same type of information as required in Box No. IV;*
(v) if, in Box No. V, the name of any State (or OAPI) is accompanied by the indication "patent of addition," or "certificate of addition," or if, in Box No. V, the name of the United States of America is accompanied by an indication "Continuation" or "Continuation-in-part":	*in such case, write "Continuation of Box No. V" and the name of each State involved (or OAPI), and after the name of each such State (or OAPI), the number of the parent title or parent application and the date of grant of the parent title or filing of the parent application;*
(vi) if there are more than three earlier applications whose priority is claimed:	*in such case, write "Continuation of Box No. VI" and indicate for each additional earlier application the same type of information as required in Box No. VI.*
2. If the applicant claims, in respect of any designated Office, the benefits of provisions of the national law concerning non-prejudicial disclosures or exceptions to lack of novelty:	*in such case, write "Statement Concerning Non-Prejudicial Disclosures or Exceptions to Lack of Novelty" and furnish that statement below.*

To Box No. VI

Item (4)

	03 February 1997	
Sweden	(03.02.1997)	9700347-9

973305

5630

PCT

WORLD INTELLECTUAL PROPERTY ORGANIZATION
International Bureau

INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification 6 : H02K 3/40

A2

(11) International Publication Number: WO 97/45926

(43) International Publication Date: 4 December 1997 (04.12.97)

(21) International Application Number: PCT/SE97/00891

(22) International Filing Date: 27 May 1997 (27.05.97)

29 Nov 98 / 30 mo

(30) Priority Data:

9602079-7	29 May 1996 (29.05.96)	SE
9602078-9	29 May 1996 (29.05.96)	SE
9700335-4	3 February 1997 (03.02.97)	SE
9700347-9	3 February 1997 (03.02.97)	SE

(71) Applicant *(for all designated States except US)*: ASEA BROWN BOVERI AB [SE/SE]; S-721 83 Västerås (SE).

(72) Inventors; and

(75) Inventors/Applicants *(for US only)*: LEIJON, Mats [SE/SE]; Hyvlargatan 5, S-723 35 Västerås (SE). BERGGREN, Bertil [SE/SE]; Rönnbergagatan 2 B, S-723 46 Västerås (SE). GERTMAR, Lars [SE/SE]; Humlegatan 6, S-722 26 Västerås (SE). NYGREN, Jan-Anders [SE/SE]; Karlfeldtsgatan 27 B, S-722 22 Västerås (SE). SÖRENSEN, Erland [SE/SE]; Gudruns väg 32, S-723 55 Västerås (SE).

(74) Agent: HOPFGARTEN, Nils; L.A. Groth & Co., KB, P.O. Box 6107, S-102 32 Stockholm (SE).

(81) Designated States: AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CU, CZ, CZ (Utility model), DE, DE (Utility model), DK, DK (Utility model), EE, ES, FI, FI (Utility model), GB, GE, GH, HU, IL, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, TJ, TM, TR, TT, UA, UG, US, UZ, VN, YU, ARIPO patent (GH, KE, LS, MW, SD, SZ, UG), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, ML, MR, NE, SN, TD, TG).

Published

Without international search report and to be republished upon receipt of that report.

(54) Title: AN ELECTRIC HIGH VOLTAGE AC MACHINE

(57) Abstract

An electric high voltage AC machine intended to be directly connected to a distribution or transmission network (16) comprises at least one winding. This winding comprises at least one current-carrying conductor, a first layer having semiconducting properties provided around said conductor, a solid insulating layer provided around said first layer, and a second layer having semiconducting properties provided around said insulating layer. In addition grounding means (18, 24, 26, 28) are provided to connect at least one point of said winding to ground.



FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	**ES**	Spain	**LS**	Lesotho	**SI**	Slovenia
AM	Armenia	**FI**	Finland	**LT**	Lithuania	**SK**	Slovakia
AT	Austria	**FR**	France	**LU**	Luxembourg	**SN**	Senegal
AU	Australia	**GA**	Gabon	**LV**	Latvia	**SZ**	Swaziland
AZ	Azerbaijan	**GB**	United Kingdom	**MC**	Monaco	**TD**	Chad
BA	Bosnia and Herzegovina	**GE**	Georgia	**MD**	Republic of Moldova	**TG**	Togo
BB	Barbados	**GH**	Ghana	**MG**	Madagascar	**TJ**	Tajikistan
BE	Belgium	**GN**	Guinea	**MK**	The former Yugoslav Republic of Macedonia	**TM**	Turkmenistan
BF	Burkina Faso	**GR**	Greece			**TR**	Turkey
BG	Bulgaria	**HU**	Hungary	**ML**	Mali	**TT**	Trinidad and Tobago
BJ	Benin	**IE**	Ireland	**MN**	Mongolia	**UA**	Ukraine
BR	Brazil	**IL**	Israel	**MR**	Mauritania	**UG**	Uganda
BY	Belarus	**IS**	Iceland	**MW**	Malawi	**US**	United States of America
CA	Canada	**IT**	Italy	**MX**	Mexico	**UZ**	Uzbekistan
CF	Central African Republic	**JP**	Japan	**NE**	Niger	**VN**	Viet Nam
CG	Congo	**KE**	Kenya	**NL**	Netherlands	**YU**	Yugoslavia
CH	Switzerland	**KG**	Kyrgyzstan	**NO**	Norway	**ZW**	Zimbabwe
CI	Côte d'Ivoire	**KP**	Democratic People's Republic of Korea	**NZ**	New Zealand		
CM	Cameroon			**PL**	Poland		
CN	China	**KR**	Republic of Korea	**PT**	Portugal		
CU	Cuba	**KZ**	Kazakstan	**RO**	Romania		
CZ	Czech Republic	**LC**	Saint Lucia	**RU**	Russian Federation		
DE	Germany	**LI**	Liechtenstein	**SD**	Sudan		
DK	Denmark	**LK**	Sri Lanka	**SE**	Sweden		
EE	Estonia	**LR**	Liberia	**SG**	Singapore		

AN ELECTRIC HIGH VOLTAGE AC MACHINE

The present invention relates to an electric high voltage AC machine intended to be directly connected to a distribution or transmission network, said machine comprising at least one winding.

Such generators with a rated voltage of up to 36 kV is described by Paul R. Siedler, "36 kV Generators Arise from Insulation Research", Electrical World, October 15, 1932, pp. 524-527. These generators comprise windings formed of medium voltage insulated conductors wherein insulation is subdivided into various layers of different dielectric constants. The insulating material used is formed of various combinations of the three components of micafolium-mica, varnish and paper.

In a publication by Power Research Institute, EPRI, EL-3391, April 1984 a generator concept is proposed for providing such high voltages that the generator can be directly connected to a power network without any intermediate transformer. Such a generator was supposed to comprise a superconducting rotor. The magnetization capacity of the superconducting field would then make it possible to use air gap windings of sufficient thickness for withstanding the electric forces. The proposed rotor is, however, of a complicated structure with a very thick insulation which considerably increases the size of the machine. In addition thereto special measures have to be taken for insulating and cooling the coil end sections.

By electric high voltage AC machines is meant, according to the present invention, rotating electric machines like generators in power stations for production of electric power, double-fed machines, outer pole machines, synchronous machines, asynchronous converter cascades, as well as power transformers. For connecting such machines, except for transformers, to distribution and transmission networks, in the following commonly

referred to as power networks, a transformer has so far been needed for transforming the voltage up to the network level, that is in the range of 130-400 kV.

By manufacturing the winding of these machines of an insulated electric high voltage conductor with a solid insulation of similar structure as cables used for power transmission the voltage of the machine can be increased to such levels that the machines can be directly connected to any power network without an intermediate transformer. Thus this transformer can be omitted. Typical working range for these machines is 30-800 kV.

For this kind of machines special attention has to be paid to grounding problems.

Grounding of generator systems and other similar electrical systems implies intentional measures for connecting an electric system to ground potential. When the so-called neutral point of the system is available it is often connected to ground, directly or through a suitable impedance. It also happens that other points in the system are connected to ground. If one point in the system is grounded the complete system is grounded as long as the galvanic connection extends.

The grounding principle used is determined by the design of the system. For a system including a generator directly connected to a Y-Δ connected step-up-transformer with the Δ-winding at the generator voltage the following grounding alternatives are most common.

- High resistance grounding
- No grounding
- Resonant grounding.

High resistance grounding is normally realized by connection of a low ohmic resistor in the secondary of a distribution transformer with the primary winding of the transformer connected from the generator neutral point to ground. Such prior art grounding is illustrated in fig. 1, which shows a generator 2 connected by a Y-Δ connected step-up transformer 3 to a network 9. The primary 11 of a

distribution transformer is connected between the neutral point of the generator 2 and ground. In the secondary 10 of the transformer a resistor 12 is connected.

The same kind of grounding can, of course, be obtained by installing a high ohmic resistor directly between the generator neutral point and ground.

An ungrounded electric system lacks any intentional connection to ground. Thus an ungrounded generator has no connection between its neutral point and ground, except for possible voltage transformers for feeding different relays and instruments.

Resonant grounding is normally also realized as illustrated in fig. 1 with the resistor 12 replaced by a reactor 12a. The reactor reactance is chosen such that the capacitive current during a line to ground fault is neutralized by an equal component of inductive current contributed for by the reactor 12a.

Also low resistance or low impedance grounding and effective grounding of the above systems are possible. Low resistance or low impedance grounding will result in lower transient overvoltages but higher ground fault currents, which can cause internal damages to the machine.

Low resistance grounding is achieved by the intentional insertion of a resistance between the generator neutral and ground. The resistance may be inserted either directly in connection to ground or indirectly, in the secondary of a transformer whose primary is connected between generator neutral and ground, cf. fig. 1.

Low impedance grounding, that is low inductance grounding is accomplished in the same way as low resistance grounding with the substitution of an inductor for the resistor. The value of the inductor in ohms is less than that required for resonant grounding, as discussed above.

For systems comprising several generators connected to a common feeding line or bus with circuit breakers between the generator terminals and the common bus low resistance or low impedance grounding is suitable.

Effectively grounding the neutral of a generator has substantially the same advantages and disadvantages as the low resistance or low impedance grounding with some differences.

A system is said to be effectively grounded if certain impedance requirements, which restricts the size of the grounding impedance, are fulfilled. In an effectively grounded system the maximum phase-to-ground voltage in unfaulted phases, in case of a ground fault, are limited to 80% of phase-to-phase voltage.

A power system network is mainly grounded through ground connections of neutral points of transformers in the system and can include no impedance (except for contact resistances), so-called direct grounding, or have a certain impedance.

Previously known grounding techniques are described in e.g. the publication IEEE C62.92-1989, IEEE Guide for the Application of Neutral Grounding in Electrical Utility Systems, Part II - Grounding of Synchronous Systems, published by the Institute of Electrical and Electronics Engineers, New York, USA, September, 1989.

If the generator neutral is grounded through a low resistance or inductance as discussed above, a path is formed for third harmonic currents from the generator neutral to ground. If a directly grounded or low-impedance grounded transformer winding or another low-impedance grounded generator is directly connected to the generator, the third harmonic currents will circulate therebetween under normal conditions.

Techniques for solving the problems of third harmonic currents in generator- and motor-operation of AC electric machines of the kind to which the present invention relates are described in Swedish patent applications 9602078-9 and 9700347-9.

The purpose of the present invention is to provide an electric high voltage AC machine suitable for direct connection to distribution or transmission networks as indicated above, which machine is provided with grounding

means suitable for different uses and operating conditions of the machine.

This purpose is obtained with an electric high voltage AC machine of the kind defined in the introductory portion of the description and having the characterising features of claim 1.

An important advantage of the machine according to the invention resides in the fact that the electric field is nearly equal to zero in the end region of the windings outside the second layer with semiconducting properties. Thus no electric fields need to be controlled outside the winding and no field concentrations can be formed, neither within the sheet, nor in winding end regions, nor in transitions therebetween.

According to an advantageous embodiment of the machine according to the invention at least two adjacent layers have substantially equal thermal expansion coefficients. In this way defects, cracks or the like as a result of thermal motions in the winding, are avoided.

According to another advantageous embodiment of the machine according to the invention said grounding means comprise means for low resistance grounding of the winding. In this way transient overvoltages as well as the ground fault current can be limited to moderate values.

According to still another advantageous embodiment of the machine according to the invention, wherein the machine has a Y-connected winding, the neutral point of which being available, high resistance grounding means comprise a resistor connected in the secondary of a transformer whose primary is connected between the neutral point and ground. In this way the resistor used in the secondary of the transformer is of comparatively low ohmic value and of rugged construction. Sufficient damping to reduce transient overvoltages to safe levels can be achieved with a properly sized resistor. Further, mechanical stresses and fault damages are limited during line-to-ground faults by the restriction of the fault current. Such a grounding device is also more economical

than direct insertion of a high ohmic resistor between the generator neutral and ground.

According to another advantageous embodiment of the machine according to the invention, wherein the machine has a Y-connected winding the neutral point of which being available, the grounding means comprises a reactor connected in the secondary of a transformer whose primary is connected between the neutral point and ground, said reactor having characteristics such that the capacitive current during a ground fault is substantially neutralized by an equal component of inductive current contributed for by the reactor. In this way the net fault current is reduced to a low value by the parallel resonant circuit thus formed, and the current is essentially in phase with the fault voltage. The voltage recovery on the faulted phase is very slow in this case and accordingly any ground fault of a transient nature will automatically be extinguished in a resonant grounded system.

According to still other advantageous embodiments of the machine according to the invention the grounding means comprise a Y-Δ grounding transformer or a so-called zigzag grounding transformer connected to the network side of the machine. The use of such grounding transformers are equivalent to low inductance or low resistance grounding with respect to fault current levels and transient overvoltages.

To explain the invention in more detail embodiments of the machine according to the invention, chosen as examples, will now be described more in detail with reference to fig. 2-11 on the accompanying drawings on which

fig. 1 illustrates prior art grounding of a synchronous generator,

fig. 2 shows an example of the insulated conductor used in the windings of the machine according to the invention,

fig. 3 shows an ungrounded three-phase machine in the form of a Y-connected generator or motor connected to a power system,

fig. 4-13 show different examples of grounding the Y-connected machine in fig. 3,
fig. 14 shows a machine according to the invention in the form of a Δ-connected generator or motor connected to a power system, and
fig. 15 illustrates the use of a grounding transformer in the system shown in fig. 14.

In fig. 2 an example is shown of an insulated conductor, which can be used in the windings of the machine according to the invention. Such an insulated conductor comprises at least one conductor 4 composed of a number of non-insulated and possibly insulated strands 5. Around the conductor 4 there is an inner semiconducting layer 6, which is in contact with at least some of the non-insulated strands 5. This semiconducting layer 6 is in its turn surrounded by the main insulation of the cable in the form of an extruded solid insulating layer 7. The insulating layer is surrounded by an external semiconducting layer 8. The conductor area of the cable can vary between 80 and 3000 mm^2 and the external diameter of the cable between 20 and 250 mm.

Fig. 3 shows schematically an ungrounded electric high voltage AC machine in the form of a Y-connected generator or motor 14 directly connected to a power system 16.

Fig. 4 shows grounding means in the form of an overvoltage protector, like a non-linear resistance arrester 18, connected between the neutral point 20 of the Y-connected machine 14 and ground. Such a non-linear resistance arrester 18 connected to the neutral point protects the insulated conductor used in the machine windings against transient overvoltages, such as overvoltages caused by a stroke of lightning.

Fig. 5 shows an embodiment with a high ohmic resistor 22 connected in parallel to the non-linear resistance arrester 18. The non-linear resistance arrester 18 is functioning in the same way in this embodiment as in the embodiment shown in fig. 4 and with

the resistor 22 a sensitive detection of ground faults by measuring the voltage across the resistor 22 is realised.

Fig. 6 shows an embodiment with high resistance grounding of the neutral point 20. In this embodiment a technique similar to the prior art described in connection with fig. 1 is used. Thus a resistor 24 is connected to the secondary 26 of a transformer with the primary winding 28 of the transformer connected from the neutral point 20 of the machine 14 to ground. The resistor 24 is comparatively low ohmic and of rugged construction, as compared to a high ohmic resistor which would be needed for direct connection between the neutral point 20 and ground for obtaining the same result. The voltage class of the resistor can consequently be reduced. Also in this case a non-linear resistance arrester 18 is connected in parallel to the primary winding 28. With this embodiment mechanical stresses and fault damages are limited during line-to-ground faults by restricting the fault current. Transient overvoltages are limited to safe levels and the grounding device is more economical than direct insertion of a resistor.

Resonant grounding of the machine can be realised in a similar way by replacing the resistor 24 by a reactor having characteristics such that the capacitive current during a line-to-ground fault is neutralized by an equal component of inductive current contributed for by the reactor. Thus the net fault current is reduced by the parallel resonant circuit thus formed and the current will be essentially in phase with the fault voltage. After extinction of the fault the voltage recovery on the faulted phase will be very slow and determined by the ratio of inductive reactance to the effective resistance of the transformer/reactor combination. Accordingly any ground fault of transient nature will automatically be extinguished in such a resonant grounded system. Thus such resonant grounding means limits the ground fault current to practically zero, thus minimising the mechanical stresses. Further continued operation of the machine can

be permitted after the occurrence of a phase-to-ground fault until an orderly shutdown can be arranged.

Fig. 7 shows an embodiment with a non-linear resistance arrester 18 connected between the neutral point 20 and ground and a grounding transformer 30 connected on the network side of the machine 14. The grounding transformer 30 is of Y-Δ design with the neutral point of the Y-connection connected to ground, whereas the Δ-winding is isolated. Grounding transformers are normally used in systems which are ungrounded or which have a high impedance ground connection. As a system component the grounding transformer carries no load and does not affect the normal system behaviour. When unbalances occur the grounding transformer provides a low impedance in the zero sequence network. The grounding transformer is in this way equivalent to a low inductance or low resistance grounding with respect to fault current levels and transient overvoltages.

The grounding transformer can also be a so-called zigzag transformer with special winding arrangements, see e.g. Paul M. Anderson, "Analysis of Faulted Power Systems", The Iowa State University Press/Ames, 1983, pp. 255-257.

Also a possible auxiliary power transformer can be used for such grounding purposes.

Fig. 8 shows an embodiment with a low ohmic resistor 32 connected between the neutral point 20 of the machine 14 and ground. The main advantage of such a low resistance grounding is the ability to limit transient and temporary overvoltages. The currents will, however, be higher in case of single phase ground faults. Also third harmonic currents will be higher in undisturbed operation.

Fig. 9 shows an alternative embodiment of the machine according to the invention in which the resistor 32 is replaced by a low inductance inductor 34 connected between the neutral point 20 and ground. Low inductance grounding works essentially in the same way as low ohmic grounding. The value of the inductor 34 in ohms is less

than that required for resonant grounding, cf. description of fig. 6.

As an alternative to the direct connection between the neutral point 20 and ground of the resistor 32 or the inductor 34, they may be indirectly connected with the aid of a transformer whose primary is connected between the neutral point 20 and ground and whose secondary contains the resistor or inductor, cf. the description of fig. 6.

In fig. 10 an embodiment is shown comprising two impedances 36 and 38 connected in series between the neutral point 20 of the machine 14 and ground, the impedance 36 having a low impedance value and the impedance 38 a high impedance value. The impedance 38 can be short-circuited by a short-circuiting device 40. In normal operation the short-circuiting device 40 is open in order to minimize third harmonic currents. In case of a ground fault the short-circuiting device 40 is controlled to short-circuit the impedance 38 and the potential in the neutral point 20 will be low and the current to ground comparatively high.

In case of an internal ground fault in the machine 14 the impedance 38 is not short-circuited. As a consequence the voltage will be high in the neutral point 20 but the current to ground will be limited. In such a situation this is to prefer since a high current can give rise to damages in this case.

To be able to cope with the problems arising from third harmonics when directly connecting an AC electric machine to a three-phase power network, i.e. when no step-up transformer is used between the machine and the network, grounding means in the form of a suppression filter 35, 37, tuned to the third harmonic together with an overvoltage protector 39 can be used, see fig. 11. The filter thus comprises a parallel resonance circuit consisting of an inductor 35 and a capacitive reactance 37. The dimensioning of the filter 35, 37 and its overvoltage protector 39 is such that the parallel circuit is capable of absorbing third harmonics from the machine

14 during normal operation, yet limiting transient and temporary overvoltages. In case of a fault the overvoltage protector 39 will limit the fault voltage such that the fault current flows through the overvoltage protector 39 if the fault is considerable. In case of a single-phase ground fault the currents will be higher as compared to e.g. the case of high resistance grounding since the fundamental impedance is low.

In fig. 12 an embodiment is shown wherein the grounding means comprises a detuned switchable third harmonics depression filter connected in parallel to an overvoltage protector 40. Such filters can be realised in several different ways. Fig. 12 shows an example comprising two inductors 42, 44 connected in series and a capacitor 46 connected in parallel to the series-connected inductors 42, 44. Further a short-circuiting device 48 is connected across the inductor 44.

The short-circuiting device 48 is controllable to change the characteristic of the filter by short-circuiting the inductor 44 when a risk for third harmonic resonance between the filter and the machine 14 and network 16 is detected. This is described more in detail in Swedish patent application 9700347-9. In this way third harmonic currents are strongly limited in normal operation. Transient and temporary overvoltages will be limited and the currents will be higher in case of a single-phase ground fault in the same way as described in connection with fig. 11.

Fig. 13 shows an embodiment wherein the neutral point 20 of the machine 14 is directly connected to ground, at 21. Such direct grounding limits transient and temporary overvoltages but results in high currents in case of ground faults. Third harmonic current flow from the neutral 20 of the machine to ground will be comparatively high in normal operation.

As a further alternative the grounding means of the machine according to the invention can comprise an active

circuit for providing a connection of the neutral point to ground having desirable impedance properties.

In fig. 14 a Δ-connected three-phase machine 50 is shown directly connected to the distribution or transmission network 16.

In such a situation a grounding transformer of the same kind as the one used in the embodiment shown in fig. 7 can be connected on the network side of the machine 50.

As in the embodiment of fig. 7 the grounding transformer can be a Y-Δ-connected transformer with the neutral point of the Y-connection ground, or a so called zigzag grounding transformer, that is a Z-0-connected transformer with the Z grounded. The grounding transformer will limit temporary overvoltages.

As in the embodiment of fig. 7 a possible auxiliary power transformer can also be used for this purpose.

CLAIMS

1. An electric high voltage AC machine, intended to be directly connected to a distribution or transmission network (16), said machine including at least one winding comprising at least one insulated current-carrying conductor (4), **characterized in** that a first layer (6) having semi-conducting properties is provided around said conductor (4), a solid insulating layer (7) is provided around said first layer, and a second layer (8) having semi-conducting properties is provided around said insulating layer, and in that grounding means (18,21,22,24,26.28,30,32,34,35,36,37,38,39,40,42,44,46,48, 52) are provided to connect at least one point of said winding to ground.

2. The machine according to claim 1, **characterized in** that the potential of said first layer is substantially equal to the potential of the conductor.

3. The machine according to claim 1 or 2, **characterized in** that said second layer is arranged to constitute substantially an equipotential surface surrounding said conductor.

4. The machine according to claim 3, **characterized in** that said second layer is connected to a predetermined potential.

5. The machine according to claim 4, **characterized in** that said predetermined potential is ground potential.

6. The machine according to any one of the claims 1, 2, 3, 4 or 5, **characterized in** that at least two adjacent layers have substantially equal thermal expansion coefficients.

7. The machine according to any one of the preceding claims, **characterized in** that said current-carrying

conductor comprises a number of strands, only a minority of said strands being non-isolated from each other.

8. The machine according to any one of the preceding claims, **characterized in** that each of said three layers is fixed connected to adjacent layer along substantially the whole connecting surface.

9. An electric AC machine having a magnetic circuit for high voltage comprising a magnetic core and at least one winding, **characterized in** that said winding is formed of a cable comprising one or more current-carrying conductors, each conductor having a number of strands, an inner semi-conducting layer provided around each conductor, an insulating layer of solid insulating material provided around said inner semi-conducting layer, and an outer semi-conducting layer provided around said insulating layer, and in that grounding means are provided to connect at least one point of said winding to ground.

10. The machine according to claim 9, **characterized in** that said cable also comprises a metall shield and a sheath.

11. The machine according to any one of the preceding claims, **characterized in** that said grounding means comprise means for direct grounding of the winding.

12. The machine according to any one of the claims 1 through 10, **characterized in** that said grounding means comprise means for low-resistance grounding of the winding.

13. The machine according to claim 12, said machine having a Y-connected winding the neutral point of which being available, **characterized in** that said low-resistance grounding means comprise a low-resistance resistor connected between the neutral point and ground.

14. The machine according to claim 12, said machine having a Y-connected winding the neutral point of which

being available, **characterized in** that said low-resistance grounding means comprise a resistor connected in the secondary of a transformer whose primary is connected between the neutral point and ground.

15. The machine according to any one of the claims 1 through 10, **characterized in** that said grounding means comprise means for low-inductance grounding of the winding.

16. The machine according to claim 15, said machine having a Y-connected winding the neutral point of which being available, **characterized in** that said low-inductance grounding means comprise a low-inductance inductor connected between the neutral point and ground.

17. The machine according to claim 15, said machine having a Y-connected winding the neutral point of which being available, **characterized in** that said low-inductance grounding means comprise an inductor connected in the secondary of a transformer whose primary is connected between the neutral point and ground.

18. The machine according to any one of the claims 1 through 10, **characterized in** that said grounding means comprise means for high-resistance grounding of the winding.

19. The machine according to claim 18, said machine having a Y-connected winding the neutral point of which being available, **characterized in** that said high-resistance grounding means comprise a high-resistance resistor connected between the neutral point and ground.

20. The machine according to claim 18, said machine having a Y-connected winding the neutral point of which being available, **characterized in** that said high-resistance grounding means comprise a resistor connected in the secondary of a transformer whose primary is connected between the neutral point and ground.

21. The machine according to any one of the claims 1 through 10, **characterized in** that said grounding means comprise means for high-inductance grounding of the winding.

22. The machine according to claim 21, said machine having a Y-connected winding the neutral point of which being available, **characterized in** that said high-inductance grounding means comprise a high-inductance inductor connected between the neutral point and ground.

23. The machine according to claim 21, said machine having a Y-connected winding the neutral point of which being available, **characterized in** that said high-inductance grounding means comprise an inductor connected in the secondary of a transformer whose primary is connected between the neutral point and ground.

24. The machine according to any one of the claims 1 through 10, said machine having a Y-connected winding the neutral point of which being available, **characterized in** that said grounding means comprise a reactor connected in the secondary of a transformer whose primary is connected between the neutral point and ground, said reactor having characteristics such that the capacitive current during a ground fault is substantially neutralized by an equal component of inductive current contributed for by the reactor.

25. The machine according to any one of the claims 1 through 10, **characterized in** that said grounding means comprise means for changing the impedance of the connection to ground in response to a ground fault.

26. The machine according to any one of the claims 1 through 10, **characterized in** that said grounding means comprise an active circuit.

27. The machine according to any one of the claims 1 through 10, **characterized in** that said grounding means

comprise a Y-Δ grounding transformer connected to the network side of the machine.

28. The machine according to any one of the claims 1 through 10, **characterized in** that said grounding means comprise a so-called zigzag grounding transformer connected to the network side of the machine.

29. The machine according to any one of the claims 1 through 10, said machine having a Y-connected winding the neutral point of which being available, **characterized in** that said grounding means comprise a suppression filter tuned for the n:th harmonic.

30. The machine according to any one of the claims 1 through 10, said machine having a Y-connected winding the neutral point of which being available, **characterized in** that said grounding means comprise a switchable suppression filter detuned for the n:th harmonic.

31. The machine according to claim 29 or 30, **characterized in** that said n:th harmonic is the third harmonic.

32. The machine according to any one of the claims 1 through 10, said machine having a Y-connected winding the neutral point of which being available, **characterized in** that said grounding means comprise an overvoltage protector connected between said neutral point and ground.

33. The machine according to any one of the claims 18 through 31, said machine having a Y-connected winding the neutral point of which being available, **characterized in** that an overvoltage protector is connected between said neutral point and ground in parallel to said grounding means.

34. A distribution or transmission network, **characterized in** that it comprises at least one machine according to any one of the claims 1 through 33.

Fig 1



NOTES:
A= High resistans grounding when Z is resistive
B= Resonant grounding when Z is inductive

Fig 2



Fig 3



Fig. 4



Fig. 5



Fig. 6



Fig. 7



Fig. 8



Fig. 9



Fig.10



Fig.11



Fig.12



Fig.13



Fig.14



Fig.15